BJ & CM Lehmann Pty. Ltd.
Trading as
Lehmann Drillers
Po Box 272, Kimba SA 5641
Ph. 088627 2304 Fax 088627 2183
ABN 53 078 291 380
www.lehmanns.com.au

A Quality Endorsed Company

TQCSI Quality Certified AU830-QC - ISO 9001:2000

BJ & CM Lehmann Pty Ltd have an OH&S Policy and Procedures in place including:

JSA's, SOP's & Operating Manuals

RC Drill Rig

Standard Design Features

Drill Mast:	9 metre rod pull capacity Capable of angles from vertical to 45° 1300mm mast dump
Diesel Engine:	Ford 6 210HP 2100 rpm
Rotation Head:	Air Drill top drive Step-less speed control 3-200 rpm low gear
Head Traverse:	Hydraulic cylinder over ropes 2:1 ratio Maximum speed 44.8 m/min upwards Maximum speed 29.6 m/min downwards
Pull Back:	(68,000 lbf)
Water Pump:	25 G.P.M
Rod Carry Rack:	Tray mounted on left hand side of back up truck Nominal capacity 33 x 6m lengths of 4" Metski Rods
Rod Handling Boom:	Hydraulically operated fully variable boom Swivels from side to side Handles all mast angles from vertical to 45°

Sample Cyclone – Trailer mounted – 20 meter hose lead

Reverse Circulation
Down Hole Hammers: 4"
5"

Optional Features

- Hydraulically powered table spanner
- Hammer Rod Breaker R/C Drill Rod Breakout Assistance Tool

Additional Equipment

- Deck mounted 1350cfm / 350 psi – 1150cfm / 500psi air compressor
- Remote Hydco Booster 1350cfm/1000psi

Carriers

- Rig – Inter Twin Steer
- Rod back up truck – Scania Bogie drive
- Booster Truck – 4x4 Hino

Manufactured at BJ & CM Lehmann Pty Ltd by:

RAGE

OPEN HOLE & WATER BORES ALSO AVAILABLE

Contact: Barry Lehmann Phone: 08 8627 2304 Mobil: 0428 272304 Fax: 08 8627 2183 Web Site: www.lehmanns.com.au Email: chris@lehmanns.com.au